

Subdivisions of T. 2 N., R. 35 E.

Chains		
	<p>high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and mountainous. 80 chs. Pine, fir and tamarack timber. Good grass. Soil, 2nd rate.</p>	
	<p>East on random between secs. 29 and 32. Var. $21^{\circ}30'$ East.</p>	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.12	<p>Intersect N. and S. line, 20 lks. S. of cor. to secs. 28, 29, 32 and 33. Thence $S.89^{\circ}51'W.$ on true line.</p>	
11.03	Gulch, course N.	-100
13.00	Top of small ridge, N.	+100
16.75	Canyon.	
25.25	Ravine.	-100
33.00	Ridge slopes W.	+150
40.06	<p>Set a stone, $14 \times 9 \times 5$ ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.</p>	
42.00	Top of ridge.	+100
58.00	Canyon.	-100
80.12	<p>To cor. to secs. 29, 30, 31 and 32. Land, mountainous. 80.12 chs. Pine, fir and tamarack timber in canyons. Good bunch grass. Soil, 3rd rate.</p>	
	<p>West on random between secs. 30 and 31. Var. $21^{\circ}30'$ East.</p>	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
76.30	<p>Intersect Township line 28 lks. N. of cor. to secs. 30, 31, 25 and 36. Thence $N.89^{\circ}48'$ East on true line.</p>	
22.00	Canyon and creek, 4 lks. wide, course N.	-400