

Subdivisions of T. 2 N., R. 35 E.

Chains	Thence West on true line. Var. 21° East.	
5.00	Gulch, course N.W.	-50
32.00	Trail on summit, N.W.	+300
40.00	Set a stone, 16x12x8 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
80.00	To cor. to secs. 19, 20, 29 and 30. Land, rough and mountainous. 80 chs. Good bunch grass. Soil, 2nd rate.	-400
	West on random between secs. 19 and 30. Var. 20° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
76.00	Intersect Township line, 30 lks. S. of cor. to secs. 24, 25, 19 and 30. Thence S. 89° 47' East on true line.	
5.50	Canyon, course N.E.	-75
12.00	Summit of ridge, course N.E.	+150
32.00	Canyon, course N.W.	-150
36.00	Set a stone, 12x12x5 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
66.50	Canyon, course S.W.	-25
76.00	To cor. to secs. 19, 20, 29 and 30. Land, mountainous. 76 chs. Soil, poor and rocky, 4th rate. Good grass.	
	North on true line between secs. 19 and 20. Var. 20° East.	
7.00	Canyon, course S.W.	
30.00	Summit of hill.	+400