

## Subdivisions of T. 2 N., R. 35 E.

Chains 40.00	Set a stone, 18x16x8 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
54.00	Draw, course East.	
63.60	Head of canyon. Ascend.	-100
80.00	Set a stone, 10x8x6 ins., 7 ins. in the ground, for cor. to secs. 17, 18, 19 and 20 marked with 5 notches on E. and 3 on S. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and mountainous. 80 chs. Good grass. Soil, 3rd rate.	
East on random between secs. 17 and 20. Var. $20^{\circ}15'$ East.		
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.00	Intersect N. and S. line, 10 lks. S. of cor. to secs. 16, 17, 20 and 21. Thence S. $89^{\circ}56'$ West on true line.	
14.00	Canyon, course N.	-600
32.50	Top of ridge, course N.	+600
40.00	Set a stone, 30x28x24 ins., 23 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
60.00	Canyon, course N.	-300
80.00	To cor. to secs. 17, 18, 19 and 20. Land, very mountainous and rough. 80 chs. Soil, 2nd rate. Good grass.	
West on random between secs. 18 and 19. Var. $20^{\circ}15'$ East.		
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	