

Subdivisions of T. 2 N., R. 35 E.

Chains 75.30	Intersect Township line, 23. lks. S. of cor. to secs. 18, 19, 13 and 24. Thence S.89°50' East on true line.	
12.50	Canyon, course N.E. Ascend.	-200
35.30	Set a stone, 20x20x14 ins., 14 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
55.50	Canyon, course N.E.	-200
66.50	Summit of ridge, course N.	+150
75.30	To cor. to secs. 17, 18, 19 and 20. Land, mountainous. 75.30 chs. No timber. Good grass. Soil, 2nd rate.	
North on true line between secs. 17 and 18. Var. 20°15' East.		
10.50	Canyon, bears N.20°W.	-50
33.40	Canyon, bears N.20°E.	-20
40.00	Set a stone, 20x10x8 ins., 14 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
47.70	Draw, course E.	
80.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for cor. to secs. 7, 8, 17 and 18 marked with 5 notches on E. and 4 on S. edges, and raised a mound of stone 2.ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and mountainous. 80 chs. Soil, rocky, 3rd rate. No timber. Bunch grass.	
East on random between secs. 8 and 17. Var. 21°30' East.		
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	