

## Allotments of T. 2 N., R. 35 E.

Chains	<p style="text-align: center;">Sec. 2</p> <p>bdy. of sec. 35, T. 3 N., R. 35 E.</p> <p>I run</p> <p>S.89°50'W. on true line parallel with N. bdy. of Tp.</p> <p style="text-align: center;">Var. 20°E.</p> <p>2.50 Gulch, course N.</p> <p>19.50 Gulch, course N.</p> <p>20.00 Intersect sec. line between secs. 2 and 3, T. 2 N., R. 35 E. Set post 3 ft. long, 3 ins. square, 24 ins. in the ground, for 1/16 sec. cor. marked 1/16 S on N. face. Dug pits, 18x18x12 ins., E. and W. of post, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land, slopes to North.</p> <p>Soil, good.</p>
	<p style="text-align: center;">Sec. 3</p> <p>From the closing corner to secs. 2 and 3 on North bdy. of Township, which is a post 4 ins. square, firmly set in the ground marked T 2 N R 35 E C C on S., S 2 on E. and S 3 on W. faces, with 2 notches on E. and 4 notches on W. edges, and mound of stone around post.</p> <p>I run</p> <p>S.89°50'W. on random line on N. bdy. of sec. 3.</p> <p style="text-align: center;">Var. 20°E.</p> <p>Setting temporary corners at 20 chains and at</p> <p>40.10 Intersect the E. and W. line at ¼ sec. cor. on S. bdy. of sec. 34, T. 3 N., R. 35 E., which is a basalt stone, 12x10x10 ins., 8 ins. in the ground, marked ¼ on N. face, and mound of stone over it.</p> <p>Thence I run</p> <p>N.89°50'E. on a true line on the N. bdy. of sec. 3.</p> <p style="text-align: center;">Var. 20°E.</p> <p>15.20 Railroad, course S.80°W.</p> <p>17.50 Wagon road.</p> <p>20.00 Set stone, 14x10x8 ins., 9 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a</p>