

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 3
	mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
23.70	Ascend bluff.
40.00	To closing corner to secs. 2 and 3 on N. bdy. of Tp. Land, rough, rocky river bottom. Balm and pine timber.
	From the $\frac{1}{4}$ sec. corner on S. bdy. of S. 34, T. 3 N., R. 35 E. I run South on true line in sec. 3. Var. 21° E.
11.20	Railroad, course N.E.
13.00	Set basalt stone, 10x8x6 ins., 7 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on W. face, and raised a mound of stone over it. Pits impracticable. Land, brushy on river bottom.
	From the $1/16$ sec. corner, 13.00 chains S. of $\frac{1}{4}$ sec. corner on South boundary of sec. 34, T. 3 N., R. 35 E. I run East on random line in sec. 3. Var. 19° E.
40.10	Intersect the $1/16$ sec. cor., 13.20 chains S. of C. corner to secs. 2 and 3, T. 2 N., R. 35 E. Thence I run West on true line in sec. 3. Var. 20° E.
15.00	Thicket in gulch, course N.
20.05	Set a stone, 12x8x7 ins., 8 ins. in the ground, for $1/16$ sec. corner, marked $1/16$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
30.00	Brink of bluff, course S. 70° W.
34.00	Foot of bluff.
40.10	To the $1/16$ sec. corner in sec. 3.