

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 4
	From 1/16 sec. corner, 10 chs. N. of corner to secs. 4, 5, 8 and 9.
	I run
	East on true line in sec. 4.
	Var. 22°E.
	Ascend.
5.00	Summit, flat.
18.50	Foot of hill.
20.00	Head of draw.
	Set post, 4 ft. long, 3 ins. square, with marked stone 12 ins. in the ground, for 1/16 sec. corner marked 1/16 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
	Land, rolling.
	Soil, 1st rate.
	Grass and weeds.
	From the 1/16 sec. corner, 30 chs. S. and 20 chs. East of ¼ sec. corner between secs. 4 and 5.
	I run
	North on true line in sec. 4.
	Var. 22°30'E.
	Along side hill sloping North.
20.00	Set post 4 ft. long, 3 ins. square, with marked stone 12 ins. in the ground, for 1/32 and 1/16 sec. corner marked 1/32 S on E. and 1/16 S on W. faces. Dug pits, 18x18x12 ins., N. and S. of post, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
25.00	Gulch, course N.10°E. Thorn thickets.
30.00	Set basalt stone, 10x8x7 ins., 7 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face, and raised a mound of stone over it. Pits impracticable.