

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 4	
	Line down a gulch. Soil, mixed 1st rate and rocky. Thorn and service brush in gulch.	
	From the $\frac{1}{4}$ sec. corner between secs. 4 and 5, the line to the center of sec. 4 being over the breaks of a heavy bluff. I began at $\frac{1}{32}$ or $\frac{1}{16}$ sec. corner, 10 chs. S. and 20 chs. E. of the $\frac{1}{4}$ sec. corner between secs. 4 and 5. Thence I run East on true line in sec. 4. Var. 21° E.	
1.50	Thorn gulch, course N.	-50
10.00	Summit, course N.	+100
18.50	Gulch, course N.	-75
20.00	Set a post 3 ft. long, 3 ins. sq., with marked stone 12 ins. in the ground, for $\frac{1}{32}$ and $\frac{1}{16}$ sec. corner marked $\frac{1}{32}$ S on W. face, and $\frac{1}{16}$ on E. face. Dug pits, 18x18x12 ins., E. and W. of post, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post. Land, rolling. Soil, 1st rate. Grass and thorn.	
	From the $\frac{1}{32}$ and $\frac{1}{6}$ sec. corner, 10 chains S. of $\frac{1}{4}$ sec. corner in the center of sec. 4 I run North on true line in sec. 4. Var. 22° East. Along the West slope. Descend.	
10.00	Set post 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ sec. corner marked $\frac{1}{4}$ on E. face. Dug pits, 18x18x12 ins., N. and S. of post, $5\frac{1}{2}$ ft. dist., and	