

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 5.
20.00	<p>Set stone, 12x10x8 ins., 8 ins. in the ground, in pasture for 1/16 sec. corner marked 1/16 on W. face, and raised a mound of stone over it. Pits impracticable.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Grass, good.</p>
20.00	<p>From the 1/16 sec. corner 20 chs. W. and 20 chs. S. of $\frac{1}{4}$ sec. corner between secs. 4 and 5.</p> <p>I run</p> <p>East on random line in sec. 5.</p> <p style="text-align: center;">Var. 19°E.</p>
20.00	<p>Intersect the N. and S. line at 1/16 sec. corner between secs. 4 and 5.</p> <p>Thence I run</p> <p>West on true line in sec. 5.</p> <p style="text-align: center;">Var. 21°E.</p>
15.00	Gulch, N.W., main canyon.
20.00	<p>To the 1/16 sec. corner.</p> <p>Line down wide gulch.</p> <p>Soil, rocky and 1st rate mixed.</p> <p>Grass and grain in field.</p>
6.00	Foot of bluff.
8.50	Top of bluff.
20.00	<p>From 1/16 sec. corner, 20 chs. West of $\frac{1}{4}$ sec. corner between secs. 4 and 5.</p> <p>I run</p> <p>West on true line in sec. 5.</p> <p style="text-align: center;">Var. 21°E.</p> <p>Set stone, 16x9x6 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5$\frac{1}{2}$ ft. dist., and raised a mound of earth 1$\frac{1}{2}$ ft. high, 3$\frac{1}{2}$ ft. base over it.</p> <p>Land, rolling.</p> <p>Soil, 1st and 2nd rate rocky. Good grass.</p> <p style="text-align: center;">June 12, 1889.</p>

†175