

## Allotments of T. 2 N., R. 35 E.

Chains	Sec. 5	
	North on true line between secs. 5 and 6.	
	Var. 21°E.	
17.00	Begin to descend.	
19.25	Foot of descent.	-100
20.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground, for 1/16 sec. corner marked 1/16 S on W. face, from which,	
	A balm, 30 ins. diam., bears W., 17 lks. dist., marked 1/16 S B T.	
	An alder, -- ins. diam., bears S.80°E., 50 lks. dist., marked 1/16 S B T.	
	Land, slopes to N., rich to top of bluff.	
	Grass and grain.	
	From the 1/16 sec. corner, 19.90 chs. E. of $\frac{1}{4}$ sec. corner between secs. 5 and 6.	
	I run	
	North on true line in sec. 5.	
	Var. 21°E.	
16.50	Road, course E. and W.	
	Graded.	
17.50	Spring branch, 10 lks. wide, course N.E.	
18.50	Railroad, course S.80°W.	
20.00	Set stone, 15x8x6 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, from which,	
	A pine, 20 ins. diam., bears N.45°E., 50 lks. dist., marked 1/16 S B T.	
	A pine, 20 ins. diam., bears S.35°W., 70 lks. dist., marked 1/16 S B T.	
	Land, brushy and rough, the N. 10 chains.	
	Timber and brush on bottom.	
	Grass and grain on foot hills.	
	West of here being so brushy I did not run the same.	
	From the corner to secs. 5, 6, 7 and 8, which is a post 4 ins. square, firmly set in ground marked T 2 N S 5 on	