

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 6
10.00	<p>From 1/16 sec. corner, 20 chs. W. of corner to secs. 5, 6, 7 and 8.</p> <p>I run North on true line in sec. 6.</p> <p style="text-align: right;">Var. 22° E.</p> <p>Descend to</p> <p>Deposited a charred stake 12 ins. in the ground. Dug pits, 18x18x12 ins., N. and S. of cor., 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit drove stake 2 ins. square, 2 ft. long, 12 ins. in the ground, marked 1/32 S on S. face.</p> <p>Land, brow of Mountain to N.</p> <p>Soil, 1st rate.</p> <p>Grass and sunflowers.</p>
10.00	<p>From the ¼ sec. corner between secs. 6 and 7.</p> <p>I run North on true line in sec. 6.</p> <p style="text-align: right;">Var. 23° E.</p> <p>Set stone, 16x12x8 ins., 12 ins. in the ground, for 1/32 sec. corner marked 1/32 on S. face, and raised a mound of stone over it. Pits impracticable.</p> <p>Land, brow of Mountain to North.</p> <p>Soil, 1st rate.</p> <p>Grass and sunflower.</p>
10.00	<p style="text-align: center;">Sec. 7</p> <p>From the ¼ sec. corner between secs. 6 and 7.</p> <p>I run South on true line in sec. 7.</p> <p style="text-align: right;">Var. 23° E.</p> <p>Gulch, course N.W.</p>
20.00	<p>Set stone, 10x8x5 ins., 6 ins. in the ground, for 1/16 and 1/32 sec. corner marked 1/16 on N. and 1/32 on S. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high,</p>