

Allotments of T. 2 N., R. 35 E.

Chains	<p style="text-align: center;">Sec. 7</p> <p>East on random line in sec. 7.</p> <p style="text-align: center;">Var. 23°E.</p> <p>20.10 Intersect the N. and S. line, 8 lks. N. of 1/16 and 1/32 sec. cor., 20 chs. S. of 1/4 sec. corner between secs. 6 and 7.</p> <p>Thence I run</p> <p>N.89°46'W. on true line in sec. 7.</p> <p style="text-align: center;">Var. 22°E.</p> <p>20.10 To the 1/32 sec. corner.</p> <p>Land, mountainous.</p> <p>Soil, rocky and 1st rate.</p> <p>Grass.</p>
	<p>From the 1/4 sec. corner between secs. 7 and 8, which is a basalt stone, 26x8x8 ins., 20 ins. in the ground, marked 1/4 on W. face, and mound of stone over it.</p> <p>Thence I run</p> <p>North on a random line between secs. 7 and 8.</p> <p style="text-align: center;">Var. 19°East.</p> <p>Setting temporary corners at every 10 and 20 chains, and at</p> <p>40.00 Intersect the corner to secs. 5, 6, 7 and 8.</p> <p>Thence I run</p> <p>South on true line between secs. 7 and 8.</p> <p style="text-align: center;">Var. 21°E.</p> <p>8.75 Road, course N.E. and S.W.</p> <p>20.00 Set stone, 15x10x7 ins., 10 ins. in the ground, for 1/16 and 1/32 sec. corner marked 1/16 on N. and 1/32 on S. face, and raised a mound of stone over it. Pits impracticable.</p> <p>25.00 Summit.</p> <p>30.00 Set basalt stone, 16x10x8 ins., 10 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face, and raised mound of stone over it. Pits impracticable.</p> <p>40.00 To the 1/4 sec. corner between secs. 7 and 8.</p>