

T. 2 N., R. 37 E. (W. bdy. T. 2, N.R., 36 E.)

Chains

A tamarack, 4 ins. in diam. bears S.71° W.17 lks.dist.  
marked T.2, N.R. 36 E. S.36 B.T.

A tamarack, 5 ins. in diam. bears N. 60° W.31 lks.  
dist., marked T 2 N R 36, E. S.25 B.T.

A spruce 3 ins. in diam. bears N. 45° E. 4 lks.  
dist., marked T.2, R.37, E. S.30 B.T.

A fir, 2 ins. in diam. bears S. 66° E. 8 lks. dist.,  
marked T.2, N.R. 37, S.31, B.T.

Land, mountainous and broken.

Soil, rocky, 4th rate.

Timber, fir, tamarack, spruce and pine.

North bet. secs. 25 and 30.

Var. 19°35' East.

Descend through dense chaparral.

15.00 Ascend through chaparral and occasional barren spots.

30.00 Summit of slightly rolling table land.

Slight descent.

40.00 Post 3 ft long, 3½ ins. square, 1 ft. in ground, marked  
¼ S on E & W faces and raised a mound of stone about  
base of post 30 inches at base and 15 inches high for  
¼ sec. cor., from which

A fir, 12 ins. in diam. bears S.5° W. 145 lks. dist.,  
marked ¼ S.B.

50.60 Brink of canyon 1000 ft. deep, course N. and for about  
3 miles ahead is a succession of rocky, precipitous  
mountain gorges, barren rocky slides, where chaining is  
impracticable so I discontinue the survey of this town-  
ship at the last ¼ sec. corner.

Land, mountainous and broken.

Soil, very rocky, 4th rate.

Timber, fir, pine and tamarack.

Sept. 29, 1881.