

## Subdivisions, T. 2 N., R. 36 E.

Chains	
	<p>no other tree within limits and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, sandy and stony, 2nd &amp; 3rd rate.</p> <p>Timber, scattering pine, fir and tamarack. Dense undergrowth of mountain laurel and wild cherry.</p>
	<hr/> <p>East on a random line bet. secs. 14 &amp; 23.</p> <p>Through timber. Var. 20° East.</p>
20.00	Bottom of gulch, about 250 ft. below cor. Course N.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.72	Intersect 55 lks. S. of the cor. to secs. 13, 14, 23 & 24.
	Thence, I run
	S. 89° 36' W. on a true line bet. secs. 14 & 23.
40.36	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on N. face, from which
	A fir, 15 ins. in diam. bears N. 65° E. 12 lks. dist., marked $\frac{1}{4}$ S. B. T.
	A fir, 5 ins. in diam. bears S. 35° E. 12 lks. dist., marked $\frac{1}{4}$ S. B. T.
80.72	The cor. to secs. 14, 15, 22 & 23.
	Land, mountainous.
	Soil, 2nd rate.
	Heavily timbered with fir, tamarack. Dense undergrowth of fir, tamarack and alder.
	<hr/> <p>From the cor. to secs. 3, 4, 33 &amp; 34 on the S. boundary, which is a basalt stone 17' x 14 x 12 ins., marked with 3 notches on E &amp; W edges, with mound of stone alongside.</p> <p>I run,</p> <p>North bet. secs. 33 &amp; 34.</p> <p>Var. 21° East.</p> <p>Over mountainous land.</p>