

Subdivisions, T. 2 N., R. 36 E.

Chains	
35.25	Meacham Creek, 50 lks. wide, runs N.E.
40.00	<p>Set a basalt stone 16 x 8 x 6 ins., 11 ins. in the ground for <math>\frac{1}{4}</math> sec. cor., marked <math>\frac{1}{4}</math> on W. face, from which,</p> <p>A pine, 26 ins. in diam. bears N.70° E. 22 lks, dist., marked <math>\frac{1}{4}</math> S.B.T.</p> <p>A fir, 6 ins. in diam. bears S. 80° W. 40 lks. dist., marked <math>\frac{1}{4}</math> S.B.T.</p>
44.00	Meacham Creek, course N.W.
62.00	Graded road bed of the Baker City Railway line, course N.30° 45' W.
63.00	Ascend mountain.
80.00	<p>Set a post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 29, 30, 31 and 32, marked T 2 N. S.29 on N.E. ; R 36 E. S32 on S.E.; S 31 on S.W., and S 30 on N.W. faces, with 1 notch on S and 5 notches on E. edges, from which</p> <p>A pine, 12 ins. in diam. bears S.30° W. 203 lks. dist., marked T 2 N.R 36 E. S31 B.T.</p> <p>A pine, 10 ins. in diam. bears N.60° W. 220 lks. dist., marked T 2 N.R.36 E. S30 B.T. ;</p> <p>no other tree within limits and raised a mound of stone around post.</p> <p>Land, mountainous and level.</p> <p>Soil, sandy loam and stony, 2nd &amp; 3rd rate.</p> <p>Timber, scattering pine, fir and tamarack. Dense undergrowth of pine, fir and buck brush.</p>
<p>East on a random line bet. secs. 29 &amp; 32.</p> <p style="text-align: right;">Var. 20° East.</p>	
Ascend mountain.	
40.00	Set temporary $\frac{1}{4}$ sec. cor.
80.50	<p>Intersect 55 lks. N. of the cor. to secs. 28, 29, 32 &amp; 33.</p> <p style="text-align: center;">Thence, I run</p> <p>N.89° 36' West on a true line bet. secs. 29 &amp; 32.</p>