

Subdivisions, T. 2 N., R. 36 E.

Chains	
40.25	<p>Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for <math>\frac{1}{4}</math> sec. cor., marked <math>\frac{1}{4}</math> S. on N. face, from which,</p> <p style="padding-left: 40px;">A pine, 6 ins. in diam. bears N. 30° E. 28 lks. dist., marked <math>\frac{1}{4}</math> S. B. T.</p> <p style="padding-left: 40px;">A fir, 7 ins. in diam. bears S. 40° E. 35 lks. dist., marked <math>\frac{1}{4}</math> S. B. T.</p>
80.50	<p>The cor. to secs. 29, 30, 31 &amp; 32.</p> <p>Land, mountainous.</p> <p>Soil, 2nd rate.</p> <p>Timber, scattering fir &amp; pine.</p> <p>Dense undergrowth of fir, pine and buck brush.</p> <p style="text-align: center;">September 30, 1882.</p> <hr/> <p>West on a random line bet. secs. 30 &amp; 31.</p> <p style="text-align: right;">Var. 20° East.</p> <p>Descend about 250 ft. to</p>
7.50	Foot of hill, course N.
8.50	Wagon road, course N.W.
10.60	Intersect Baker City Railway line, course N.W.
20.60	Meacham Creek, 50 lks. wide, runs N.
20.75	Ascend hill.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
92.10	<p>Intersect W. boundary of township at a point 75 lks. S. of the cor. to secs. 30, 31, 25 &amp; 36, which is a post 4 ins. square, marked: T 2 N. S 30 on N.E.; R 36 E.S. 31 on S.E.; R 35 E.S 36 on S.W., and S 25 on N.W. faces, with 1 notch on S. and 5 notches on N. edges, from which,</p> <p style="padding-left: 40px;">A cottonwood, 7 ins. in diam. bears S. 65° W. 39 lks. dist., marked T 2 N.R. 35 E. S36 B.T.,</p> <p style="padding-left: 40px;">and a mound of stone around post.</p> <p style="text-align: center;">Thence, I run</p> <p>S.89° 32' E. on a true line bet. secs. 30 &amp; 31</p>