

## Subdivisions, T. 2 N., R. 36 East

Chains

which is level.

Soil, sandy loam and stony 2nd and 3rd rate.

Timber, scattering fir and pine.

North bet. secs. 19 & 20.

Var. 19-3/4° E.

26.50 Bottom of gulch, about 300 ft. below sec. cor., course W.

40.00 Set a basalt stone 13 x 9 x 5 ins., 8 ins. in the ground  
for 1/4 sec. cor., marked 1/4 on W. face and raised a  
mound of stone alongside.

41.50 Top of ridge, about 200 ft. above gulch, course W.

58.00 Bottom of gulch, about 200 ft. below ridge, course W.

80.00 Top of ridge, about 300 ft. above gulch, course W.

Set a post 4 ft. long, 4 ins. square, 24 ins. in the  
ground for cor. to secs. 17, 18, 19 & 20, marked  
T 2 N.S. 17 on N.E.; R 36 E. S20 on S.E.; S 19 on S.W.  
and S 18 on N.W. faces, with 3 notches on S. and 5  
notches on E. edges, from which

A fir, 6 ins. in diam. bears N. 55° E. 100 lks.  
dist., marked T 2 N.R. 36 E. S17, B.T.

A pine, 7 ins. in diam. bears S 20° E. 55 lks. dist.,  
marked T 2 N.R. 36 E. S 20 B.T.

A pine, 5 ins. in diam. bears S. 60° W. 7 lks. dist.,  
marked T2 W.R.36 E. S 19 B.T.

A pine, 6 ins. in diam. bears N. 50° W. 57 lks.  
dist., marked T 2 N.R 36 E. S18 B.T.

Land, mountainous.

Soil, stony, 3rd rate.

Timber, scattering fir and pine. Good bunch grass.

East on a random line bet. secs. 17 & 20.

Var. 16° East.

Descend about 300 ft. to