

Retracement of

T. 2 N., R. 36 East. (Subdivisions)

Chains	
81.45	<p>Intersect cor. of secs. 23 and 24, described heretofore. Land, mountainous. Soil, stony and loam; 3rd and 2nd rate. Timber, pine, fir, spruce, larch, cottonwood and tamarack. Undergrowth, yew, mountain laurel, huckleberry and small firs. Mountainous land, 81.45 chs.</p>
	<p>From the cor. of secs. 22 and 23, described heretofore, I run, S. 89° 43' W. bet. secs. 15 and 22 on old line over plateau through scattering timber.</p>
1.00	<p>Summit of divide bet. Meacham Creek and Umatilla Tributaries, bears N. and S. Descend.</p>
4.00	<p>Steeper descent.</p>
40.13	<p>Intersect old $\frac{1}{4}$ sec. cor., which is a stone loosely set, marked as described by the Surveyor General. No trace of a fir, described as a bearing tree, can be found. I reset the stone at the same point and, raise mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, N. of the cor. Pits impracticable.</p>
63.45	<p>Heavy timber and undergrowth bears N. & S.</p>
65.45	<p>Foot of mountains, 300 ft. below ridge, bears N. 10° W. Rine Creek, 10 lks. wide, swift current, sandy bottom, course N. 10° W. Ascend steep E. slope of mountain.</p>
76.00	<p>Summit of divide, 300 ft. high, bears N. and S. Enter scattering timber bears N and S. Descend.</p>
78.23	<p>Intersect the closing cor. of secs. 15 and 16, established by me June 29, 1901.</p>
80.18	<p>Intersect the old cor. of secs. 21 and 22, described heretofore. Land, mountainous. Soil, loam and stony, 2nd and 3rd rate. Timber, pine, fir, tamarack, spruce, yew and alder. Undergrowth, small</p>