

T. 2 N., R. 36 East W. M.

Chains	firs, mountain laurel, huckleberry, vine maple and wild cherry.
	Mountainous land, 80.18 chains.
	July 4, 1901.
	I commence at the cor. of secs. 7, 12, 13 and 18, on the E. bdy. of T. 2 N., R. 36 E., which was established by me June 18, 1901.
	Thence, I run
	West on sectional correction line bet. secs. 12 and 13.
	Ascend E. slope of mountain through scattering pine timber and dense undergrowth.
11.25	Leave dense undergrowth, bears N. and S.
21.00	Top of grassy spur, bears N.W. and S.E.
	Ascend along slope of spur.
40.00	Set an iron stone, 18 x 12 x 8 ins., 12 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, from which
	A fir, 12 ins. in diam. bears N. 40° E., 9 lks. dist., marked $\frac{1}{4}$ S. 12 B.T.
	A fir, 12 ins. in diam., bears S. 50° E., 12 lks. dist., marked $\frac{1}{4}$ S. 13 B.T.
	This cor. stands about 350 ft. above the Umatilla River.
70.25	Leave timber, bears N.W., S.E.
75.00	Summit of divide, bet. Meacham Creek and S. Fork Umatilla River, 1000 ft. high, bears N. 10° E., S. 60° W.
	Pass over plateau on summit of divide.
78.40	Pack trail to Gibbons, bears N.20° E., S.30° W.
79.75	Enter timber, bears N.E., S. 70° W.
80.00	Set basalt stone, 24 x 10 x 7 ins., 12 ins. in the ground, for cor. of secs. 11, 12, 13 and 14, marked with 1 notch on E., and 4 notches on S. edges, from which
	A fir, 15 ins. in diam., bears N. 60° E., 15 lks. dist., marked T. 2 N., R. 36 E., S.12 B.T.
	A fir, 24 ins. in diam., bears S.24° E., 20 lks. dist., marked T. 2 N., R. 36 E., S. 13, B. T.