

Subdivisions, T. 2 N., R. 36 E.

| | |
|--------|---|
| Chains | |
| 80.00 | <p>Set ironstone, 20 x 15 x 12 ins., 15 ins. in the ground for cor. to secs. 9, 10, 15 and 16, marked with 4 notches on S. and 3 notches on E. edges, from which</p> <p>A fir, 10 ins. in diam. bears N.86° E., 91 lks. dist., marked T. 2 N., R. 36 E. S. 10 B.T.</p> <p>A fir, 10 ins. in diam., bears S. 43° E., 71 lks. dist., marked T. 2 N., R. 36 E., S. 15, B. T.</p> <p>A fir, 12 ins. in diam., bears S. 7° W., 299 lks. dist., marked T. 2 N., R. 36 E., S. 16, B.T.</p> <p>A fir, 5 ins. in diam. bears N. 18° W., 109 lks. dist., marked T. 2 N., R. 36 E., S. 9, B. T.</p> <p>This corner stands about 400 ft. above Rine Creek.</p> <p>Land, mountainous.</p> <p>Soil, gravelly and loam; 3rd and 2nd rate.</p> <p>Timber, pine, fir and tamarack.</p> <p>Undergrowth, mountain laurel, willow and alder.</p> <p>Mountainous land, 80.00 chs.</p> <p style="text-align: right;">June 22, 1901.</p> |
| | <hr/> <p>June 24: At 7^h 50^m a.m., l. m. t., I set off 45° 40' on the lat. arc; 23° 26' N. on the decl. arc; and determine a true meridian with the solar at the cor. of secs. 9, 10, 15 and 16,</p> <p style="text-align: center;">Thence, I run</p> <p>W. on sectional correction line bet. secs. 9 and 16.</p> <p>Ascend steep E. slope of mountain through scattering timber and undergrowth.</p> |
| 11.50 | Leave timber and undergrowth, bears N. 20° W., S. 60° E. |
| 16.50 | Summit of ridge, 500 ft. high, bet. Rine Creek and Thompson Creek, bears N. and S. |
| | Descend into Thompson basin. |
| 16.70 | Pack trail, bears N. and S. |
| 23.75 | Enter heavy fir timber and undergrowth, bears N.20° W., S. 45° E. |
| 37.75 | Spring branch, 1 lk. wide, in deep ravine, course S.60°W. |