

Subdivisions, T. 2, N., R. 36 E.

Chains	
62.50	Enter heavy timber, bears N.W., S.E.
71.00	Leave timber, bears N. and S.
79.50	Summit of ridge, 1000 ft. high, bet. Line Creek and Meacham Creek, bears N. 60° W., S.30° E.
	Descend W. slope.
81.68	Intersect Umatilla Indian Reservation Bdy., 4.99 chs. N.20° E. of the closing cor. to secs. 17 and 18, which is a basalt stone, 24 x 20 x 4 ins., lying loosely in a scattered mound of stone, and marked as described by the Surveyor General. I reestablished this old cor. at the same point. Set basalt stone, 24 x 20 x 4 ins., 18 ins. in the ground for closing cor. to secs. 17 and 18, marked C. C. on S. face. Raise mound of stone 2 ft. base, 1½ ft. high, S. of cor. Pits impracticable.
81.68	At a point 4.99 chs N. 20° E. of the old closing cor. to secs. 17 and 18, I set basalt stone 20 x 10 x 8 ins., 15 ins. in the ground for closing corner to secs. 8 and 17, marked C.C. on E. face and U. I. R. on W. face. Raise mound of stone, 2 ft. base, 1½ ft. high, E. of cor. Pits impracticable.
83.39	Intersect the N. and S. line 3.59 chs. N. of the cor. of secs. 7, 8, 17 and 18, which is nearly destroyed. The true point for said cor. is clearly shown by the mound, but the cor. stone is missing, having, according to all probability, rolled down the steep hill side. I re-establish this cor. at the same point as follows: Set basalt stone 15 x 10 x 8 ins., 10 ins. in the ground, for cor. of secs. 7, 8, 17 and 18, marked with 4 notches on S. and 5 notches on E. edges. Raise mound of stone, 2 ft. base, 1½ ft. high, W. of cor. Pits impracticable.
	Land, mountainous.
	Soil, stony and loam; 4th and 2nd rate.
	Timber, pine, fir, tamarack and alder.
	Undergrowth, service berry, huckleberry and chaparral.
	Mountainous land 81.68 chs.

June 24, 1901.