

Subdivisions, T. 2, N., R. 36 E.

Chains	
73.50	Pack trail, bears E. and W.
75.50	Descend N. slope of hill, through scattering timber, bears N. 70° E., S. 70° W.
80.00	Set basalt stone, 15 x 10 x 5 ins., 10 ins. in the ground, for cor. of secs. 1, 2, 11 and 12, marked with 5 notches on S. and 1 notch on E. edges, from which A fir, 12 ins. in diam. bears N. 18° E., 130 lks. dist., marked T 2 N., R. 36 E., S. 1 B.T. A fir, 12 ins. in diam. bears S. 49° E., 103 lks. dist., marked T. 2 N., R. 36 E., S. 12, B.T. A fir, 16 ins. in diam., bears S. 46° W., 15 lks. dist., marked T. 2 N., R. 36 E., S. 11, B.T. A fir, 16 ins. in diam. bears N. 62½° W., 11 lks. dist., marked T. 2 N., R. 36 E., S. 2, B.T. This sec. cor. stands about 20 ft. below the plateau. Land, nearly level. Soil, rich loam, 1st rate. Timber, fir, pine, tamarack and spruce. Heavily timbered land, 75.00 chs. <p style="text-align: right;">June 25, 1901.</p>
	June 26: At 7 ^{h.} 30 ^{m.} A.M., l.m.t., I set off 45° 40½' on the lat. arc, 23° 24' N. on the decl. arc, and de- termine a true meridian with the solar at the cor. of secs. 1, 2, 11 and 12. Thence, I run E. on random line bet. secs. 1 and 12.
40.00	Set temp. ¼ sec. cor.
80.10	Intersect E. bdy. of Tp. 15 lks. N. of the cor. of secs. 1, 6, 7 and 12, which was set by me June 18, 1901. Thence, I run N. 89° 54' W, on true line bet. secs. 1 and 12. Descend through scattering timber.
5.50	Dry bed of stream, 10 lks. wide, course S. 30° E. Water comes out just below line. Ascend E. slope of mountain.