

Subdivisions, T. 2, N., R. 36 E.

Chains	
	<p>A fir, 10 ins. in diam., bears S. 15° E., 35 lks. dist., marked T.2 N., R. 36 E. S.2, B. T.</p> <p>A pine, 20 ins. in diam., bears S. 45° W., 210 lks. dist., marked <math>\frac{1}{4}</math> S.3, T.2,N.,R.36,E.,S.3,B.T.</p> <p>Thence, I run</p> <p>S.0° 02' E. on true line bet. secs. 2 and 3.</p> <p>Descend through scattering timber.</p>
8.10	<p>Branch of Rine Creek, 10 lks. wide, slow current, course N. 40° W.</p> <p>Ascend steep N. slope of ridge.</p>
10.00	<p>Enter heavy timber, bears E. and W.</p>
32.00	<p>Set basalt stone, 24 x 12 x 12 ins., 18 ins. in the ground for <math>\frac{1}{4}</math> sec. cor., marked <math>\frac{1}{4}</math> on W. face, from which</p> <p>A fir, 12 ins. in diam., bears N.10° E., 37 lks. dist., marked <math>\frac{1}{4}</math> S. 2, B.T.</p> <p>A fir, 10 ins. in diam., bears N. 16° W., 16 lks. dist., marked <math>\frac{1}{4}</math> S. 3 B.T.</p> <p>This cor. stands about 500 ft. above the creek.</p>
46.25	<p>Summit of ridge, 575 ft. above creek, bears N.65° W.</p> <p>Descend steep S. slope.</p> <p>Leave timber, bears E. and N. 40° W.</p>
61.00	<p>Enter scattering timber and undergrowth, bears E. and W.</p>
63.25	<p>Ravine, 200 ft. deep, course S. 80° W.</p> <p>Ascend N. slope of hill.</p>
72.00	<p>The cor. of secs. 2, 3, 10 and 11.</p> <p>Land, mountainous.</p> <p>Soil, loam and gravelly; 2nd and 3rd rate.</p> <p>Timber, fir, pine, spruce, tamarack, willow, alder and cherry.</p> <p>Undergrowth, small willows and firs, vine maple, huckleberry and laurel.</p> <p>Mountainous land, 72.00 chs.</p> <p>Overcast at noon, prevented taking lat.</p> <p style="text-align: right;">June 28, 1901.</p>