

Subdivisions, T. 2 N., R. 36 E.

Chains 42.91	Set basalt stone, 15 x 6 x 6 ins., 10 ins. in ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face. Raise mound of stone W. of cor. Pits impracticable.
46.25	Top of ridge point, 200 ft. above Rine Creek, bears N.80° W.  Descend steep N. slope of hill, through occasional patches of undergrowth.
71.00	Foot of hill.  Ravine, 300 ft. deep, course S. 70° W. Ascend steep, rocky S. slope of ridge.
82.91	The cor. of secs. 8, 9, 16 and 17.  Land, mountainous. Soil, stony, 3rd rate. Timber, pine and fir. Undergrowth, laurel, huckle berry and dog-wood. Mountainous land, 82.91 chs.
	N. 0° 04' W. bet. secs. 8 and 9. Ascend steep S. slope of ridge.
10.25	More gradual ascent.
28.20	Top of ridge, 500 ft. above ravine, course N. 60° W.
28.25	Pack trail to Gibbon, bears N.60° W., S. 60° E.  Descend steep N. slope of ridge.
35.00	Enter undergrowth, bears E. and W.
36.00	Enter scattering timber, bears E. and W.
40.00	Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, marked $\frac{1}{4}$ S. 8, on W. face and S. 9 on E. face, from which  A fir, 8 ins. in diam., bears S. 44° E., 37 lks. dist., marked $\frac{1}{4}$ S.B.T.  A pine, 8 ins. in diam., bears N. 85° W., 82 lks. dist., marked $\frac{1}{4}$ S., B.T.  This cor. stands about 200 ft. below top of ridge.
47.00	Foot of hill.  Dry bed of stream, 10 lks. wide, course N. 35° W.