

West Bdy. Township 2 S., R.31 E., W.M.  
 As surveyed by David P. Thompson, Deputy Surveyor,  
 Under Contract No. 106, Dated Aug. 16, 1864.

Chains	***** Note: In the absence of any instructions as how this line should be run, I continue running S. on W. Bdy. of T. 2 S., R.31 E.	Feet
	S. on W. Bdy. of Secs. 6. Var. 20°40' E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, trench, etc. as per instructions.	
80.00	Set stone, 17 x 15 x 5 for Cor. to Secs. 6, 7, 1 & 12. Land; rolling. Soil; 2nd rate.	
	S. on W. Bdy. of Sec. 7. Var. 22° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor. in mound of earth with charred stake, pits, trench, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 12, 13, 7 & 18, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; gently rolling. Soil; good 2nd rate. Oct. 3, 1864.	
	S. on W. Bdy. of Secs. 18. Var. 19° 45' E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 18, 19, 13 & 24, in mound of earth, with charred stake, pits, trench, etc. as per instructions. Land; rolling. Soil; good 2nd rate.	
	S. on W. Bdy. of Secs. 19. Var. 19° E.	
40.00	Set stone, 15 x 12 x 6 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 14 x 12 x 10 ins. for Cor. to Secs. 24, 25, 19 & 30.	