

Subdivisional Lines, T.2 S., R.30 $\frac{1}{2}$ E., W.M.

Chains		Feet
20.00	Road to timber, course N.W. & S.E.	- 60
	A house brs. N.42° W., also	
	" " " S.67° E.	
21.00	Ravine, course from S.E. to N.W.	
40.00	Set stone, 17 x 12 x 5 on S.W. hillside in mound of stone for $\frac{1}{4}$ Sec. Cor.	
	1st house brs. S.32° W.	
	2nd " " S.21° E.	
80.00	Set stone, 16 x 12 x 7 on level in mound of stone and drove stake for Cor. to Secs. 25, 26, 35 & 36.	
	Land; surface rolling.	
	Soil; 1st & 2nd rate. Good grass, good for farming. The above mentioned houses are not occupied at present. The owners were driven away by the Indians and have not yet returned. I did not learn the owner's names.	
	E. on a random line bet. Secs. 25 & 36.	
	Var. 20° 45' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.92	Intersected E. Bdy., 78 lks. S. of Cor. to Secs. 25 & 36, from which Cor., I run	
	S.89° 27' W. on true line bet. Secs. 25 & 36.	
	Var. 24° 30' E.	
	James M. Rice's house brs. S.20° W.	
10.00	" " " " " S.3° E.	
11.50	Ravine, course from S. to N.	- 60
39.96	Set stone, 20 x 14 x 5 on N.E. slope for $\frac{1}{4}$ Sec. Cor.	+ 60
79.92	The Cor. to Secs. 25, 26, 35 & 36.	+ 20
	Land; surface undulating.	
	Soil; 1st & 2nd rate. Good grass. Good for farming purposes.	
	W. on random line bet. Secs. 26 & 35.	
	Var. 20° 45' E.	
11.60	Intersected W. Bdy., 22 lks. N. of stone Cor. to fractional Secs. 26 & 35, from which Cor., I run	
	N.88° 54' E. on true line bet. Secs. 26 & 35.	