

Exterior Bdys. of Tp. 2 S., R.31 E., W.M.
As surveyed by David P. Thompson, U.S. Deputy Surveyor,
Under Contract No. 106, dated Aug. 16, 1864.

Chains		Feet
	E. on S. Bdy. of Sec. 31.	
	Var. 19°45' E.	
40.00	Set stone, 24 x 10 x 4 ins., for $\frac{1}{4}$ Sec. Cor.	
53.00	Deep ravine, course N.	
80.00	Set stone, 22 x 12 x 4 ins., for Cor. to Secs. 31, 32, 5 and 6.	
	Land; rough and broken.	
	Soil; 2nd rate.	
	E. on S. Bdy. of Sec. 32.	
	Var. 19° E.	
25.00	Ravine brs. N.	
40.00	Set stone, 20 x 8 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
60.00	Ravine brs. N.	
80.00	Set post for Cor. to Secs. 32, 33, 4 & 5, in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
	Land; very broken.	
	Soil; 2nd rate. Fine grass.	
	E. on S. Bdy. of Sec. 33.	
	Var. 20° E.	
37.00	Ravine brs. N.W.	
40.00	Set stone, 18 x 12 x 6 ins., for $\frac{1}{4}$ Sec. Cor.	
60.00	Descend into deep rocky canyon.	
80.00	Set stone, 24 x 18 x 12 ins., for Cor. to Secs. 33, 34, 3 & 4.	
	Land; hilly.	
	Soil; 2nd rate.	
	E. on S. Bdy. of Sec. 34.	
	Var. 25° E.	
5.00	Deep canyon and creek, 7 lks. wide, course N. Ascend	1000
40.00	Set stone, 18 x 12 x 5 ins., for $\frac{1}{4}$ Sec. Cor.	
55.00	Top of hill, brs. N. & S. Descend.	700
73.00	Foot of hill. Ascend.	200