

Exterior Bdys. T. 2 S., R. 31 E., W.M.

Chains		Feet
	N. on E. Bdy. of Sec. 12.	
	Var. 20° 50' E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
80.00	Set stone, 17 x 15 x 5 ins., for Cor. to Secs. 6, 7, 1 & 12. Land; level. Soil; 2nd rate.	
	N. on E. Bdy. of Sec. 1.	
	Var. 22° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
80.00	Set post for Cor. to Tps. 1 & 2 S., Rs. 31 & 32 E., in mound of earth, with charred stake, pits, trench, etc., as per instructions.	
	Oct. 5, 1864.	
	Extracts from Subdivisional Lines, T. 2 S., R. 32 E., W.M. As surveyed by John C. Arnold, U.S. Deputy Surveyor. Under Contract No. 551, Dated March 19, 1890.	
	W. on a random line bet. Secs. 30 & 31.	
	Var. 20° 05' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	" " Cor. to Secs. 25, 30, 31 & 36.	
	Finding no traces of any old Cor., I commenced at S.W. Cor. to this Tp., which is a post, 4 x 4 ins., 24 ins. above ground, marked R. 31 S. 36 on N.W. face. No other visible marks, in mound of earth, 1 $\frac{1}{2}$ ft. high x 4 ft. base on N. hillside, 200 lks. E. of a ravine, N.E.	
	Thence I run	
	N. on W. Bdy. of Sec. 31. Descend.	
	Var. 18° 45' E.	
21.00	Stanley Creek canyon; N. 75° W. Ascend.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.96	Intersect E. & W. line, 25 lks. E. of Cor. to Secs. 25, 30, 31 & 36, on W. Bdy. of Tp., which is a basalt stone, 18 x 15 x 10 ins., lying loose on ground on W. slope.	