

## Subdivisional Lines, T.2 S., R.31 E., W.M.

Chains		Feet
	W. on true line bet. Secs. 26 & 35. Descend hill.	
15.00	Brook, 5 lks..wide, runs N.	-250
39.75	Set stone, 24 x 12 x 8 for $\frac{1}{4}$ Sec. Cor.	
40.00	Foot of hill. Ascend.	
79.50	The Cor. to Secs. 26, 27, 34 & 35.	+450
	Land; hilly. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 22 & 23.	
	Descend Hill. Var. $21\frac{1}{2}^{\circ}$ E.	
40.00	Set stone, 17 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 22 x 8 x 6 for Cor. to Secs. 14, 15, 22 & 23.	+250
80.00	Land; rolling soil; 2nd rate, 22, 26 & 27.	
<hr/>		
	E. on random line bet. Secs. 14 & 23.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.68	Intersect N. & S. line, 14 lks. S. of Cor. to Secs. 13, 14, 23 & 24, from which Cor., I run	
	S. $89^{\circ} 54'$ W. on true line bet. Secs. 14 & 23. Descend hill.	
21.00	Brook, 4 lks. wide, runs N. Foot of hill. Ascend.	-200
39.84	Set stone, 22 x 10 x 8 for $\frac{1}{4}$ Sec. Cor. Top of hill.	+275
71.25	Ravine and spring, runs N.	
79.68	The Cor. to Secs. 14, 15, 22 & 23.	
	Land; hilly. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 14 & 15.	
	Ascend hill. Var. $20^{\circ}$ E.	
40.00	Set stone, 20 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	
50.00	Top of hill. Descend hill	+300
80.00	Set stone, 18 x 15 x 5 for Cor. to Secs. 10, 11, 14 & 15.	+200
	Land; hilly. Soil; 2nd rate.	
<hr/>		
	E. on random bet. Secs. 11 & 14.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.84	Intersect N. & S. line, 21 lks. N. of Cor. to Secs. 11, 12, 13 & 14, from which, I run	
	N. $89^{\circ} 51'$ W. on true line bet. Secs. 11 & 14.	