

Subdivisional Lines, T. 2 S., R.31 E., W.M.

| Chains | | Feet |
|---|--|-------------|
| 37.00 | Foot of hill. Creek, 8 lks. wide, runs N.5° W. Ascend a- long W. slope of hill | 600 |
| 40.00 | Set stone, 18 x 16 x 10 for $\frac{1}{4}$ Sec. Cor. | |
| 80.00 | Set stone, 42 x 18 x 15 for Cor. to Secs. 27, 28, 33 & 34. Land; very steep and stony. Soil; 3rd rate. | 700 |
| E. on random line bet. Secs. 27 & 34. | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.46 | Intersect N. & S. line, 56 lks. N. of Cor. to Secs. 26, 27, 34 & 35, from which, I run N.89° 36' W. on true line bet. Secs. 27 & 34. Descend hill. | |
| 40.23 | Set stone, 22 x 8 x 5, for $\frac{1}{4}$ Sec. Cor. | |
| 47.50 | Ravine brs. N. | |
| 80.46 | The Cor. to Secs. 27, 28, 33 & 34. Land; hilly. Soil; 2nd rate. | 850 |
| Nov. 19, 1864. | | |
| N. bet. Secs. 27 & 28. | | |
| Ascend hill. | | Var. 19° E. |
| 40.00 | Set stone, 18 x 8 x 8, for $\frac{1}{4}$ Sec. Cor. | |
| 50.00 | Top of hill, brs. N.W. & S.E. Descend. | 150 |
| 80.00 | Set post for Cor. to Secs. 21, 22, 27 & 28, in mound of earth, with charred stake, pits, etc., as per instruct- ions. | 400 |
| Land; rolling. Soil; 2nd rate. Very good grass. | | |
| E. on random line bet. Secs. 22 & 27. | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.64 | Intersect N. & S. line, 35 lks. N. of Cor. to Secs. 22, 23, 26 & 27, from which Cor., I run N.89° 45' W. on true line bet. Secs. 22 & 27. | |
| 3.00 | Ravine brs. N.E. | |
| 40.32 | Set stone, 18 x 17 x 8, for $\frac{1}{4}$ Sec. Cor. | |
| 53.00 | Ravine brs. N. | |
| 80.64 | The Cor. to Secs. 21, 22, 27 & 28. Land; rough and broken. Soil; poor 2nd rate. | |