

Subdivisional Lines, T. 2 S., R.31 E., W.M.

Chains		Feet
	N. bet. Secs. 21 & 22.	
	Descend hill. Var. $20\frac{1}{2}^{\circ}$ E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
42.64	Spring brook, 2 lks. wide, runs N.W.	
80.00	Set post for Cor. to Secs. 15, 16, 21 & 22, in mound of earth, with charred stake, pits, etc., as per instructions.	450
	Land; hilly. Soil; 2nd rate. Good grass.	
<hr/>		
	E. on random line bet. Secs. 15 & 22.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.48	Intersect N. & S. line, 28 lks. N. of Cor. to Secs. 14, 15, 22 & 23, from which, I run	
	N. $89^{\circ} 48'$ W. on true line bet. Secs. 15 & 22. Ascend hill.	
40.24	Set stone, 20 x 6 x 6 for $\frac{1}{4}$ Sec. Cor.	
80.48	The Cor. to Secs. 21, 22, 15 & 16.	300
	Land; hilly. Soil; 2nd rate.	
<hr/>		
	N. bet. Secs. 15 & 16.	
	Var. $21\frac{1}{2}^{\circ}$ E.	
17.00	Brook, 3 lks. wide, runs N.E. Foot of hill. Ascend.	150
40.00	Set stone, 18 x 18 x 8 for $\frac{1}{4}$ Sec. Cor.	
50.00	Top of hill brs. N.E. & S.W. Descend.	300
62.00	Brook, 3 lks. wide, runs N.E. Foot of hill. Ascend.	300
80.00	Set stone, 14 x 10 x 5 for Cor. to Secs. 9, 10, 15 & 16.	150
	Land; rough and broken. Soil; 3rd rate.	
<hr/>		
	E. on a random line bet. Secs. 10 & 15.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. Var	
80.35	Intersect N. & S. line, 34 lks. N. of Cor. to Secs. 10, 11, 14 & 15, from which Cor., I run	
	N. $89^{\circ} 45'$ W. on true line bet. Secs. 10 & 15. Descend hill.	
40.18	Set stone, 16 x 12 x 12 for $\frac{1}{4}$ Sec. Cor.	
54.60	Foot of hill. Creek, 8 lks. wide, runs N.E. Ascend hill.	500
80.35	The Cor. to Secs. 9, 10, 15 & 16.	150