

Subdivisional Lines, T. 2 S., R.31 E., W.M.

Chains		Feet
40.80	Set stone, 18 x 8 x 4 for $\frac{1}{4}$ Secs. Cor.	
41.00	Ravine brs. N. Foot of hill. Ascend.	-300
80.80	The Cor. to Secs. 19, 20, 29 & 30. Land; hilly. Soil; good 2nd rate.	+300
<hr/>		
	N. bet. Secs. 19 & 20. Descend hill. Var. $19\frac{3}{4}^{\circ}$ E.	
40.00	Set stone, 20 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.	
55.30	Brook, 3 lks. wide, runs N.E. Foot of hill. Ascend.	-250
80.00	Set stone, 24 x 8 x 6 for Cor. to Secs. 17, 18, 19 & 20. Land; rolling. Soil; 1st rate.	+150
<hr/>		
	E. on random line bet. Secs. 17 & 20.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.50	Intersect N. & S. line, at Cor. to Secs. 16, 17, 20 & 21, from which Cor., I run W. on a true line bet. Secs. 17 & 20;	
15.00	Brook, 3 lks. wide, runs N.E.	
40.25	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
41.40	Brook, 3 lks. wide, runs N.E. Ascend hill.	
80.50	The Cor. to Secs. 17, 18, 19 & 20. Land; generally level. Soil; good 2nd rate. Nov. 21, 1864.	+150
<hr/>		
	W. on random line bet. Secs. 18 & 19.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersect W. Bdy. at Cor. to Secs. 18 & 19, from which, I run E. on true line bet. Secs. 18 & 19. Descend hill.	
40.80	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.80	The Cor. to Secs. 17, 18, 19 & 20. Land; rolling. Soil; good 2nd rate.	-200