

Subdivisional Lines, T. 2 S., R. 32 E., W.M.

| Chains |   | Feet |
|--------|---|------|
| 80.27  | Intersect N. Bdy., 27 lks. E. of Cor. to Secs. 1 & 2, from which, I run   |      |
|        | S.0°12' E. on true line bet. Secs. 1 & 2. Descend hill.   |      |
| 27.40  | Foot of hill. Ascend.   |      |
| 40.27  | Set stone, 18 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.  | 200  |
| 66.00  | Top of hill brs. E. & W. Descend.   | 500  |
| 80.27  | The Cor. to Secs. 1, 2, 11 & 12.<br>Land; hilly. Soil; 2nd rate. Fine grass.  |      |
|        | W. on true line bet. Secs. 23 & 26. Descend hill.   |      |
| 37.00  | Foot of hill. Brook, 3 lks. wide, runs N. Ascend hill.  | 500  |
| 40.00  | Set stone, 24 x 12 x 5, for $\frac{1}{4}$ Sec. Cor.   |      |
| 80.00  | Set stone, 20 x 10 x 8, for Cor. to Secs. 22, 23, 26 & 27.<br>Land; hilly. Soil; 2nd rate.                              | 700  |
|        | N. bet. Secs. 22 & 23.<br>Descend hill. Var. 22° E.   |      |
| 40.00  | Set stone, 18 x 9 x 5, for $\frac{1}{4}$ Sec. Cor.  |      |
| 80.00  | Set stone, 20 x 10 x 6, for Cor. to Secs. 14, 15, 22 & 23.<br>Land; hilly. Soil; 2nd rate.                              | 600  |
|        | E. on random line bet. Secs. 14 & 23.   |      |
| 40.00  | Set post for temp. $\frac{1}{4}$ Sec. Cor.  |      |
| 80.32  | Intersect N. & S. line, 27 lks. N. of Cor. to Secs. 13, 14, 23 & 24, from which, I run                                  |      |
|        | N.89°48' W. on true line bet. Secs. 14 & 23. Descend hill.  |      |
| 40.00  | Set stone, 20 x 20 x 6 for $\frac{1}{4}$ Sec. Cor.  |      |
| 80.32  | The Cor. to Secs. 14, 15, 22 & 23.<br>Land; hilly. Soil; 2nd rate.  |      |
|        | N. bet. Secs. 14 & 15.<br>Var. 21 $\frac{1}{2}$ ° E.<br>Descend hill.   |      |
| 40.00  | Set stone, 18 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.   |      |
| 80.00  | Set stone, 18 x 16 x 8 for Cor. to Secs. 10, 11, 14 & 15.<br>Land; on N. slope of mountain. Soil; 2nd rate. Good grass. |      |