

North Bdy., T. 3 S., R.33 E., W. M.

Chains		Feet
42.00	Descend hill, brs. N. & S.	
57.80	Spring branch, 2 lks. wide, in canyon, course N., 500 ft. deep & ascend.	
62.00	Top of ridge, brs. N. & S., 150 ft. high and descend.	
67.00	Spring branch, 2 lks. wide, runs N.E. & ascend.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 1, 2, 35 &amp; 36, marked</p> <p style="padding-left: 40px;">T.2 S., R. 33 E., S.36 on N.E.</p> <p style="padding-left: 40px;">T.2 S.,R.33 E., S.35 on N.W.</p> <p style="padding-left: 40px;">T.3 S.,R.33 E., S.2 on S.W.</p> <p style="padding-left: 40px;">T.3 S., R.33 E.,S.1 on S.E. with 1 notch on E. and 5 notches on W. faces; from which,</p> <p style="padding-left: 40px;">A pine, 18 ins. diam., brs. N.38°E., 26 lks. dist., marked T.2 S., R.33 E., S.36,B.T.</p> <p style="padding-left: 40px;">A fir, 5 ins. diam., brs. N.40° W., 33 lks. dist., marked T.2 S., R.33 E., S.35,B.T.</p> <p style="padding-left: 40px;">A fir, 36 ins. diam., brs. S.27° W., 11 lks. dist., marked T.3 S., R.33 E., S. 2,B.T.</p> <p style="padding-left: 40px;">A pine, 9 ins. diam., brs. S.34° E., 75 lks. dist., marked T.3 S., R.33 E., S.1,B.T.</p> <p>At top of hill, brs. N.E. &amp; S.W., 500 ft. above last brook. Land; broken &amp; mountainous.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p>Dense undergrowth of pine and fir.</p>	
	W. on N. Bdy. of Sec.2	
	Var. 19° E.	
38.50	Descend hill, brs. N.20° W.	
40.00	<p>Set basalt stone, 12 x 8 x 7 ins., 8 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face, from which,</p> <p style="padding-left: 40px;">A pine, 36 ins. diam., brs. S.48° E., 43 lks. dist., marked <math>\frac{1}{4}</math> S.,B.T.</p> <p style="padding-left: 40px;">A fir, 24 ins. diam., brs. N.46° W., 45 lks. dist., marked <math>\frac{1}{4}</math> S.,B.T.</p>	
45.00	Leave timber, brs. N. & S.	