

North Bdy., T. 3 S., R. 33 $\frac{1}{2}$  E., W.M.

| Chains  | Feet   |
|---|--|
|   | A tamarack, 9 ins. diam., brs. S.31° W., 100 lks. dist.,<br>marked $\frac{1}{4}$ S., B.T.  |
| 80.00   | Set basalt stone, 16 x 10 x 10 ins., 11 ins. in ground,<br>for Cor. to Secs. 1, 2, 35 & 36, marked with 1 notch<br>on the E. and 2 notches on W. edges, from which,<br>A pine, 18 ins. diam., brs. N.54° E., 50 lks. dist.,<br>marked T.2 S., R.33 $\frac{1}{2}$ E., S.36, B.T.<br>A pine, 10 ins. diam., brs. S.29° E., 75 lks. dist.,<br>marked T.3 S., R.33 $\frac{1}{2}$ E., S.1, B.T.<br>A pine, 10 ins. diam., brs. S.51° W., 36 lks. dist.,<br>marked T.3 S., R.33 $\frac{1}{2}$ E., S.2, B.T.<br>A pine, 20 ins. diam., brs. N.48° W., 37 lks. dist.,<br>marked T.2 S., R.33 $\frac{1}{2}$ E., S.35, B.T.<br>Land; hilly & Soil 2nd rate.<br>Heavily timbered with pine, fir and tamarack, 80 chs. |
|   | S.89° 46' E. on true line bet. Secs. 1 & 36.<br>Var. 20° E.  |
| 40.00   | Set basalt stone, 16 x 16 x 3 ins., 11 ins. in ground, for<br>$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which,<br>A pine, 30 ins. diam., brs. S.41° E., 202 lks. dist.,<br>marked $\frac{1}{4}$ S., B.T.<br>A pine, 18 ins. diam., brs. N.36° E., 234 lks. dist.,<br>marked $\frac{1}{4}$ S., B.T.  |
| 60.00   | Wagon road, course N. & S.   |
| 80.00   | The Cor. to Tps. 2 & 3 S., Rs. 33 $\frac{1}{2}$ & 34 E.<br>Land; rolling. Soil; 2nd rate.<br>Heavily timbered with pine, and fir, 80 chs.  |
| General Description.  |  |
| The land in this Tp. is high and mountainous, covered with<br>a fine quality of timber. |  |
| Dec. 1, 1882.   |  |
| North Bdy., T. 3 S., R. 33 E., W.M.   |  |