


Exterior & Subdivisional Lines, T.2 S., R. 33 E., W. M.
 As surveyed by John C. Arnold, U.S. Deputy Surveyor,
 Under Contract No. 551,
 Dated March 19, 1890.

Chains	
	<p>I commence at Closing Cor. to Secs. 13 & 14, on Reservation Bdy., which is a pine post, 3 x 3 ins., marked  on E., UR on S. and CC on W. faces, in mound of stone, 1 ft. high x 2 ft. base on summit of high, stony ridge, course N.W. & S.E.</p>
	Lat. 45°23'N.
	<p>Thence I run S. bet. Secs. 13 & 14.</p>
	Var. 20°30'E.
1.03	<p>Daly wagon road, N.W. & S.E. Descend.</p>
9.00	<p>Ravine, course W. by S. Ascend.</p>
15.00	<p>Summit. Descend.</p>
36.17	<p>Set basalt stone, 24 x 10 x 6 ins., 18 ins. in ground, for $\frac{1}{2}$ Sec. Cor., marked $\frac{1}{2}$ on W. face; dug pits, 18 x 18 x 12 ins., N. & S. of Cor., $5\frac{1}{2}$ ft. distant. Raised mound of earth and stone, 2 ft. high by 4 ft. base over Cor., on hillside facing E.</p>
64.20	<p>A basalt boulder, 25 ft. high.</p>
66.67	<p>Canyon, course S. S. W. Ascend.</p>
76.17	<p>Set basalt stone, 18 x 12 x 4 ins., 13 ins. in ground, for Cor. to Secs. 13, 14, 23 & 24, marked with 3 notches on N. and one notch on E.; raised mound of stone, 2 ft. high by $4\frac{1}{2}$ ft. base over Cor., on steep W. hillside, from which,</p> <p style="padding-left: 40px;">A pine, 50 ins. diam., brs., up hill, N.E., 197 lks. dist., marked T2SR33ES13BT.</p> <p style="padding-left: 40px;">A pine, 40 ins. diam., brs. S. 70° W., in canyon, 250 lks. dist., marked T2SR33ES23BT</p> <p>No other tree in limits.</p> <p>A basalt stone, in place, 17 x 17 x 17 ins., above ground, brs. S.E., in Cor. Sec. 24, dist. 33 lks.</p>