

Exteriors & subdivisional Lines, T.2 S., R.33 E., W. M.

Chains	<p>Land; mountainous & stony, 76.17 chs. Scattering timber, pine & fir in canyons. Good grass. Soil; 4th rate.</p> <p style="text-align: right;">Sept. 17, 1890.</p>
40.00	<p>E. on random line bet. Secs. 13 & 24. Var. 20°00'E.</p> <p>Set temp. $\frac{1}{4}$ Sec. Cor.</p>
80.36	<p>Intersect E. Bdy. of Tp., 71 lks. S. of Cor. to Secs. 13, 18, 19 & 24, which is a basalt stone, 12 x 8 x 5 ins., in mound of stone, 1 ft. high x 2 ft. base, and marked with 3 notches on N. and 3 notches on S. faces, on S.W. hillside.</p> <p>Thence I run S. 89°30' W. on true line bet. Secs. 13 & 24. Var. 19°30'E.</p>
18.36	<p>Descend.</p> <p>Deep canyon, course S.W. Ascend.</p>
32.80	<p>Summit of ridge, falls S.W. Descend.</p>
40.18	<p>Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Dug pits, 18 x 18 x 12 ins., E. and W. of stone, 5 $\frac{1}{2}$ ft. distant. Raised mound of stone & earth, 3 ft. high by 4 ft. base around Cor., on hillside facing W.</p>
46.70	<p>Canyon, course S.W. Ascend.</p>
72.36	<p>Summit. Descend.</p>
80.36	<p>The Cor. to Secs. 13, 14, 23 & 24. Land; mountainous, 80.36 chs. Some grass, mostly on W. slopes. Soil; 4th rate.</p> <p style="text-align: right;">Sept. 20, 1890.</p>