

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W. M.

Chains	E. on random line bet. Secs. 24 & 25. Var. 20°15'E. Ascend 22 chs.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
79.60	Intersect E. Bdy. of Tp., 30 lks. N. of Cor. to Secs. 19, 24, 25 & 30, which is a basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, marked with 4 notches on N. and 2 notches on S., in mound of stone, 2 ft. high x 2 $\frac{1}{2}$ ft. base, on S. hillside. Thence I run N. 89°47'W. on true line bet. Secs. 24 & 25. Var. 19°30'E. Ascend.
5.00	Summit. Descent steep & stony.
24.60	Enter timber
28.60	Wagon road, brs. N.W. & S.E.
29.30	Birch Creek, 20 lks. wide, runs N.W. Ascend steep mountain through brush and timber.
39.80	Set basalt stone, 18 x 12 x 8 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of stone, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high x 4 ft. base over Cor., from which, A fir, 8 ins. diam., brs. N. 15 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 10 ins. diam., brs. S. 26 lks. dist., marked $\frac{1}{4}$ S., B.T.
50.60	Leave timber.
57.60	Summit. Descend.
79.60	The Cor. to Secs. 23, 24, 25 & 26. Land; mountainous. & broken. Soil; 4th rate. Good grass. Timber; pine, fir & larch. Undergrowth; same, 26 chs. The whole line runs over mountainous land. Lat. 45°22' N.