

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
40.25	Birch Creek, 20 lks. wide, course S.70° W.	
40.50	Enter timber and brush.	
42.50	Ascend steep mountain.	
60.00	Leave brush.	
73.75	Arnold's Peak, brs. W., 120 lks. to base & 275 lks. to highest point. Summit. Descend.	1000
80.00	Set basalt stone, 20 x 10 x 8 ins., 15 ins. in ground, for Cor. to Secs. 22, 23, 26 & 27, marked 4 notches on N. face and 2 notches on E. face. Raised mound of stone, 2 ft. high x 4½ ft. base over Cor., on S. side of mountain. Pits impracticable.	
	Lat., by my instrument, N.45°22'.	
	Scattering pine and fir on N. slopes; same timber, with undergrowth, along Birch Creek., 19,50 chs.	
	Soil; 4th rate. Good grass. The whole line runs over mountainous land.	
	E. on random line bet. Secs. 23 & 26.	
		Var.20°30'E.
	Descend steep mountain.	
40.00	Set temp. ¼ Sec. Cor.	
80.40	Intersect N. & S. line at Cor. to Secs. 23, 24, 25 & 26.	
	Thence I run	
	W, on true line bet. Secs. 23 & 26.	
	Descend.	Var.20°15'E.
24.60	Spring branch, brs. S.50 lks; dist. , on W. face of hill.	
40.20	Set basalt stone, 18 x 10 x 6 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face and raised mound of stone, 2 ft. high x 3½ ft. base over Cor., on hillside facing W. Pits impracticable.	
47.40	Foot of mountain. Cabin brs. N.50 lks. dist.	
47.80	Wagon road, course N.&& S.	
48.90	Birch Creek, 12 lks. wide, course N.	
51.40	Ascend steep mountain.	
80.40	The Cor. to Secs. 22, 23, 26 & 27.	
	Soil; stony 5th rate. Good grass on N. & E.slopes.	