

## Exterior &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	E. on random line bet. Secs. 15 & 22.	
	Descent, steep & stony. Var. 14°00' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.75	Intersect N. & S. line, 50 lks. N. of Cor. to Secs. 15, 16, 21 & 22.	
	Sept. 15, 1891.	
	Thence I run	
	N.89° 39' W. on true line bet. Secs. 15 & 22.	
	Ascend. Var. 17°30' E.	
6.25	Summit of ridge falls S. Descend	+300
39.88	Set basalt stone, 14 x 8 x 8 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone $1\frac{1}{2}$ ft. high x $4\frac{1}{2}$ ft. base over Cor. Fits impracticable.	
57.25	Ravine, course S.W. Ascent stony 45°	--500
61.25	Summit of ridge falls S.5°E. Descend.	
68.25	Wagon road, course N.W. & S.E.	
69.25	Enter brush at foot of steep, stony mountain.	
71.75	Birch Creek, 20 lks. wide, runs S.W.	
76.25	Leave brush.	
77.10	Pole fence, N. & S. Foot of hill. Ascend. 45°	
79.75	The Cor. to Secs. 15, 16, 21 & 22. Land; mountainous & stony, 73.25 chs. Dense brush; cottonwood, cherry & thorn, 6.50 chs.. Soil on creek bottom, rich; elsewhere 5th rate. Good grass.	
	S. bet. Secs. 21 & 22.	
	Descend 45°. Var. 14°00' E.	
4.00	Pole fence N.20° E. & S.20° W.	
9.00	Enter timber & brush.	
14.00	Foot of mountain. Ascend.	
15.00	Leave timber and brush. Enter field.	
18.65	Leave field, rail fence N.W. & S.E.	
20.00	Ascend abruptly 35°. Enter brush.	
25.00	Leave brush. Enter scattering timber.	
40.00	Set basalt stone, 18 x 12 x 4 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone.	