

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	4 notches on E., and raised mound of stone, 2 ft. high by 4½ ft. base over stone on S. hillside. Pits impracticable. John Horn's house brs. S.E. about 15.00 chs. Land; mountainous & stony, 80.chs. No timber. Soil; 5th rate.	
	E. on random line bet. Secs. 9 & 16. Var. 20°00' E.	
	Descend.	
9.50	Canyon, course S.W.	-150
40.00	Set temp. ¼ Sec. Cor.	
80.78	Intersect N. & S. line, 5 lks. S. of Cor. to Secs. 9, 10, 15 & 16. Thence I run, S. 89° 58' W. on true line bet. Secs. 9 & 16. Var. 19°45' E.	
6.00	Ravine, course S.W.	-250
15.00	Summit of ridge falls S.	
21.00	Canyon, course S.	
31.00	Summit of ridge falls S.W.	
40.39	Set basalt stone, 18 x 6 x 5 ins., 12 ins. in ground, for ¼ Sec. Cor., marked ¼ on N. face. Raised mound of stone 2 ft. high x 3½ ft. base over stone on S. hillside. Pits impracticable.	
80.78	The Cor. to Secs. 8, 9, 16 & 17. Land; mountainous & stony, 80.78 chs. Soil; 5th rate. Scattering pine and fir timber in canyons.	
	S. bet. Secs. 16 & 17. Descend. Var. 20°00' E.	
9.50	Wagon road brs. E. & W.	
10.00	Enter field, fence brs. E. & W.	
13.50	Leave " " " " " " Enter dense brush & timber.	
14.70	Bireh Creek, 15 lks. wide, course N. 80° W.	
15.00	Ascend steep, brushy mountain.	
27.50	Leave brush and timber.	