

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	marked U.R. on N. face, C.C. on S. face and raised mound of stone, $2\frac{1}{2}$ ft. high x 4 ft. base over the stone, on S. hillside. Pits impracticable.	
80.00	Set basalt stone, 18 x 14 x 6 ins., 12 ins. in ground, for Cor. to Secs. 5, 6, 7 & 8, marked 5 notches on S. face, 5 notches on E. face, and raised mound of stone, $2\frac{1}{2}$ ft. high x 4 ft. base over Cor., on S. face of hill. Pits impracticable.	
	Soil; stony, 4th rate. Some grass.	
	The whole line runs over mountainous land.	
	Sept. 21, 1891.	
	E. on random line bet. Secs. 5 & 8.	
	Var. $19^{\circ}45'E$.	
	Ascend 10° .	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.95	Intersect N. & S. line, 47 lks. S. of Cor. to Secs. 4, 5, 8, & 9.	
	Thence I run Ascend.	
	S. $89^{\circ}40'W$. on true line bet. Secs. 5 & 8.	
	Var. $18^{\circ}45'E$.	
4.45	Summit of ridge falls S. $20^{\circ}W$. Descend.	
25.95	Canyon, S. $20^{\circ}W$. Ascend 40° .	-900
39.98	Set basalt stone, 16 x 10 x 8 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; dug pits, 18 x 18 x 12 ins., E. & W. of stone, $5\frac{1}{2}$ ft. dist. Raised mound of stone & earth, $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on S. hillside.	
67.45	Summit of ridge falls S. $15^{\circ}W$. Descend.	
79.95	The Cor. to Secs. 5, 6, 7 & 8.	
	Land; mountainous, 79.95 chs.	
	Soil; stony 4th rate. No timber. Good grass.	
	W. bet. Secs. 6 & 7. Descend.	
	Var. $19^{\circ}45'E$.	
9.00	Ravine S. $15^{\circ}W$. Ascend 36° .	-100.