

## Exterior. &amp; Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains		Feet
	1½ ft. high x 3½ ft. base over Cor. on S. hillside. Pits impracticable.	
44.00	Ravine, course N.W. Ascend 15°	-150
51.50	Summit of ridge falls N.50°W. Descend 45°	+200
76.00	Canyon, N.70°W. Ascend 45°	-300
80.00	Set basalt stone, 12 x 8 x 6 ins., 8 ins. in ground, for Cor. to Secs. 19, 20, 29 & 30, marked 2 notches on S. & 5 notches on E. edges; dug pits, 18 x 18 x 12 ins., in each Sec. Cor., 5½ ft. dist. Raised mound of earth, 2 ft. high x 4½ ft. over Cor. Land; mountainous, 80.00 chs. Soil; 3rd & 5th rate. Scattering pine & fir & brush in canyons. Good grass.	
	E. on random line bet. Secs. 20 & 29. Var. 20°00' E.	
40.00	Set temp. ¼ Sec. Cor. Sept. 24, 1891.	
80.78	Intersect N. & S. line at Cor. to Secs. 20, 21, 28 & 29. Thence I run	
	W. on true line bet. Secs. 20 & 29. Ascend.	
3.50	Summit of ridge falls N.20°E. Descend.	
16.00	Ravine, course S.50°E. Ascend.	
36.50	Summit of ridge falls N.20°E. Descend.	
40.39	Set basalt stone, 14 x 8 x 6 ins., 8 ins. in ground, for ¼ Sec. Cor. (could dig no deeper), marked ¼ on N. face. Raised mound of stone, 1½ ft. high x 3½ ft. base over Cor., on W. side of mountain. Pits impracticable.	
80.78	The Cor. to Secs. 19, 20, 29 & 30. Land; mountainous, 80.78 chs. Soil; stony 5th rate. No timber. Good grass.	
	W. bet. Secs. 19 & 30. Ascend 15°. Var. 20°00' E.	
9.00	Summit of ridge falls N.W. Descend 32°	+350
24.75	Enter field, brush, fence N.W. & S.E.	