

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains			Feet
	S. bet. Secs. 29 & 30.	Ascend 30° Var. 20°00' E.	
15.00	Summit of ridge falls N.W.	Descend 28°	+300
23.50	Canyon, course W.	Ascend 28°	-200
38.00	Summit of ridge falls N.35°W.	Descend 35°	+400
40.00	Set basalt stone, 12 x 10 x 5 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. Raised mound of stone, $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on W. face of hill Pits impracticable.		
62.75	Canyon, course W.	Ascend 34°	-325
73.00	Summit of ridge falls W.	Descend 35°	+250
80.00	Set basalt stone, 16 x 8 x 4 ins., 6 ins. in ground (digging impracticable), for Cor. to Secs. 29, 30, 31 & 32, marked 1 notch on S. and 5 notches on E. Raised mound of stone $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor. on S. hillside. Land; mountainous & stony, 80.00 chs. Soil; 5th rate. No timber, Good grass.		
		Sept. 26, 1891	
	E. on random line bet. Secs. 29 & 32.	Var. 19°45' E.	
	Ascend 35°.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.		
80.20	Intersect N. & S. line, 28 lks. N. of Cor. to Secs. 28, 29, 32 & 33. Thence I run,	Descend.	
	N.89°48' W. on true line bet. Secs. 29 & 32.		
2.70	South Canyon, N.	Ascend 25°	-1800
14.70	Summit of ridge falls N.	Descend 30°	+400
21.45	Canyon, N.E. course.	Ascend 38°	-900
23.70	Leave timber.		
40.20	Set basalt stone, 10 x 8 x 8 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face. Raised mound of stone $1\frac{1}{2}$ ft. high x $3\frac{1}{2}$ ft. base over Cor., on E. side of mountain. Pits impracticable.		
43.70	Summit of mountain.	Descend 45°	+1200
80.20	The Cor. to Secs. 29, 30, 31 & 32.		