

Exterior & Subdivisional Lines, T.2 S., R.33 E., W.M.

Chains	Feet.
	<p>marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 20 ins. diam., brs. N.42°E., 110 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>I run, thence W. on N. Bdy. of Sec.5.</p> <p style="text-align: right;">Var. 18°30' E.</p> <p>Descend.</p>
8.00	Draw, course N.20°W.
8.88	<p>Intersect E. Bdy. of Tp. 2 S., R.32 E., 135 lks. N. of line, post, marked 20 on S. side, on old blazed line. I find the topography, at this point, to agree with original notes, and, again, diligently search for Closing Tp. Cor. as reported in notes, but find no traces of any such Cor. In this vicinity, at certain seasons of the year, there are frequent and fearful water spouts, as they are called, hence, it is probable, that the Cor. stone reported, has been carried away by one of them.</p> <p>At point of intersection, I Set basalt stone, 18 x 12 x 10 ins., 12 ins. in ground, for Closing Cor. to T.2 S., R.32 E., marked 6 notches on N. and S. faces and C.C. on E. face, in a draw, on W. slope, among among clumps of alder and willow brush, from which, A tamarack, 18 ins. diam., brs. N.40°15' E., 19 lks. dist., marked T.2 S., R.33 E., S.31, C.C., B.T. A fir, 18 ins. diam., brs. N.18°15' W., 29 lks. dist., marked T.2 S., R.32 E., S.36, B.T.</p> <p>See letter dated Aug.8th, 1892.</p> <p style="text-align: right;">July, 25th, 1892.</p>
<hr/> General Description <hr/>	
<p>The surface of this Tp. is exceedingly rough and mountainous, the soil varying from 3rd to 5th rate, excepting along Birch Creek, which is paralleled by a belt of very rich land, varying in width from 5 to 40 chs., & on which are located some good houses and fine fruit</p>	