

Exterior Lines of T.2 S., R.33 E., W.M.
 As surveyed by James P. Currin & James E. Noland, U.S. Deputy Surveyor
 Under their Special Contract, Dated May 4th, 1887.

Chains		Feet
	Commencing at the Cor. to Tps. 2 S., R.33 E., 3 S., R.33 $\frac{1}{2}$ E. and 2 & 3 S., R.34 E., which is a post, 48 x 4 x 4 ins., 24 ins. above ground, marked T.2 S., S.31 on N.E. R.34 E., S.6 on S.E. T.3 S., S.1 on S.W. and R.33 $\frac{1}{2}$ E., S.36 on N.W. edges with 6 notches on N., S., E. & W. edges, from which, A pine, 11 ins. diam., brs. N.65° E., 39 lks. dist., marked T.2 S., R.34 E., S.31, B.T. A willow, 6 ins. diam., brs. S.76° E., 38 lks. dist., marked T.3 S., R.34 E., S.6, B.T. A tamarack, 27 ins. diam., brs. S.43° W., 11 lks. dist., marked T.3 S., R.33 $\frac{1}{2}$ E., S.1, B.T. A pine, 11 ins. diam., brs. N.24° W., 36 lks. dist., marked T.2 S., R.33 $\frac{1}{2}$ E., S.36, B.T.	
	I run N. bet. Secs. 31 & 36. Var. 15° E.	
2.50	Leave timber, enter prairie.	
19.50	Wagon road, course S.E.	
32.80	Intersected U.R.Bdy., 4.94 chs. W. of 67 $\frac{1}{2}$ M. post. Set basalt stone, 12 x 10 x 10 ins., 8 ins. in ground, marked U.R.C.C. for Closing Cor. on Tp. line. Raised mound of stone alongside. Pits impracticable.	
33.00	Enter dense underbrush.	
40.00	A spruce, 8 ins. diam., which I marked $\frac{1}{4}$ S. on W. face, for $\frac{1}{4}$ Sec. Cor., from which, A spruce, 8 ins. diam., brs. N.30° E., 13 lks. dist., marked $\frac{1}{4}$ S., B.T. A spruce, 6 ins. diam., brs. S.85° W., 19 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.00	Set basalt stone, 12 x 10 x 8 ins., 8 ins. in ground, for Cor. to Secs. 25, 30, 31 & 36, marked 1 notch on S. & 5 notches on N. edges. From which, A pine, 12 ins. diam., brs. N.20° E., 133 lks. dist., marked T.2 S., R.34 E., S.30, B.T.	