

Subdivisional Lines, T.2 S., R.33 E., W. M.

| | |
|--------|--|
| Chains | A pine, 12 ins. diam., brs. N.35°E., 83 lks. dist., marked $\frac{1}{4}$ S., B.T. |
| | A pine, 12 ins. diam., brs. N.20°W., 34 lks. dist., marked $\frac{1}{4}$ S., B.T. |
| 48.25 | Canyon, N. |
| 70.00 | Summit of ridge, N. |
| 80.30 | To Cor. to Secs. 1, 2, 11 & 12. |
| | Land; broken & mountainous, 80,30 chs. Soil; 4th rate. |
| | Pine timber on W. side of canyons. Good bunch grass. |
| | S. bet. Secs. 11 & 12. Var. 21°45'E. |
| 28.00 | Ravine, W. |
| 37.50 | Canyon, N.W. |
| 40.00 | Set stone, 12 x 14 x 20 ins., 14 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, from which, |
| | A pine, 20 ins. diam., brs. N.50°E., 29 lks. dist., marked $\frac{1}{4}$ S., B.T. |
| | A fir, 18 ins. diam., brs. S.50°W., 29 lks. dist., marked $\frac{1}{4}$ S., B.T. |
| | Raised mound of stone, 18 ins. high, with 3 $\frac{1}{2}$ ft. base along-side. |
| 65.00 | Summit of ridge, N.W. |
| 80.00 | Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 11, 12, 13 & 14, marked |
| | T 2 S S 12 on N.E. |
| | R 33 E S 13 on S.E. |
| | S 14 on S.W. and |
| | S 11 on N.W. faces, from which, |
| | A fir, 4 ins. diam., brs. N.45°E., 20 lks. dist., marked T 2 S S 12 B T. |
| | A pine, 4 ins. diam., brs. S.45°W., 23 lks. dist., marked R 33 E S 14 B T. |
| | A fir, 10 ins. diam., brs. N.30°W., 69 lks. dist., marked S 11 B T. |
| | No other trees in limits. Raised mound of stone, 2 ft. high with 4 $\frac{1}{2}$ ft. base alongside. |
| | Land; broken. Scattering pine & fir timber. Bunch grass on open ridges. Soil; 3rd rate. |
| | E. on random line bet. Secs. 12 & 13. Var. 20°E. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Intersect line at Cor. to Secs. 12 & 13 at E. Bdy. Var. 19°E. |