

Subdivisional Lines, T.2 S., R.33 E., W. M.

Chains	Thence W. on true line.
15.20	Head of canyon, S.E.
30.00	Summit of ridge. Trail N. & S.
40.00	Set stone, 6 x 8 x 16 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ on N. face, from which, A pine, 12 ins. diam., brs. S.20°W., 1.51 chs. dist., marked $\frac{1}{4}$ S., B.T. A pine, 18 ins. diam., brs. N.68°W., (dist. lost), marked $\frac{1}{4}$ S., B.T. And over which, I raised mound of stone, 18 ins. high, with $3\frac{1}{2}$ ft. base.
43.50	Ravine, N.W.
51.10	" S.W.
60.20	Canyon, N.
70.00	Ravine, N.
80.00	To Cor. to Secs. 11, 12, 13 & 14. Land; rough & mountainous, 80 chs. Soil; rocky. Some grass.
	July 20, 1887.
	S. bet. Secs. 13 & 14. Ascend. Var. 20°E.
3.83	Intersect U.R. Bdy., 14,94 chs., N.25°W. of $\frac{1}{2}$ mile Cor. in 72nd mile. Set basalt stone, 10 x 10 x 10 ins., 7 ins. in ground, for Closing Cor. to Secs. 13 & 14, marked U.R., C.C. on N. face, over which I raised mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base. Land; mountainous, 3.83 chs. Soil; 4th rate; rocky.
	From Cor. to Secs. 2, 3, 34 & 35 on N. Bdy. of Tp., I run S. on true line bet. Secs. 2 & 3. Var. 19°30'E.
26.75	Canyon, E.
40.00	Set basalt stone, 7 x 8 x 9 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, around which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.
55.00	Gulch, W.
80.00	Set basalt stone, 8 x 10 x 12 ins., 8 ins. in ground, for Cor. to Secs. 2, 3, 10 & 11, marked 2 notches on E. and 5 on S. edges; dug pits, 18 x 18 x 12 ins., in each Sec., $5\frac{1}{2}$ ft. dist. Raised mound of earth, 2 ft. high with $4\frac{1}{2}$ ft. base alongside. Land; broken. Scattering pine timber. Good grass. Soil; 1st rate.