

## Subdivisional Lines, T. 2 S., R. 33 E., W.M.

Chains	Feet
	S. 89°55' W. on true line.
	Var. 20° E.
5.95	Intersect U.R. Bdy., 7.06 chs., N. 58° W, of the Closing Cor. on the Reservation line bet. Secs. 13 & 14. Set basalt stone, 10 x 10 x 12 ins., 8 ins. in ground, for U.R. Closing Cor., marked U.R., C.C. on E. face, over which I raised mound of stone, 2 ft. high with 4½ ft. base.
25.46	Intersect U.R. Bdy., 19.51 chs. W. of last Closing Cor. & 2.48 chs., S. 80° W. of the 72d mile monument and Set basalt stone, 8 x 10 x 16 ins., 12 ins. in ground, for U.R. Closing Cor., marked U.R. C.C., around which I raised mound of stone, 2 ft. high with 4½ ft. base.
40.10	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for ¼ Sec. Cor., marked ¼ S. on N. face, over which I raised mound of stone, 18 ins. high, with 4½ ft. base. Descend.
80.20	To Cor. to Secs. 10, 11, 14 & 15. Land; rolling & very rocky. Soil; 4th rate. No grass.
	S. on true line bet. Secs. 14 & 15. Var. 20° E. Ascend.
6.08	Intersect U.R. Bdy., 3.00 chs., S. 78° 30' W. of ⅛ on U.R. Bdy. and Set basalt stone, 16 x 10 x 6 ins., 10 ins. in ground, for U.R. Closing Cor., marked U.R., C.C. on N. face, over which I raised mound of stone, 2 ft. high with 4½ ft. base. Land; rolling. Soil; 4th rate and rocky, no grass.
	From Cor. to Secs. 3, 4, 33 & 34 on N. Bdy. of Tp., I run S. on true line bet. Secs. 3 & 4. Var. 19° 30' E.
40.00	Set basalt stone, 16 x 12 x 10 ins., 10 ins. in ground, for