

Exteriors, T.2 S., R.35 E., W. M.
As surveyed by Jacob C. Cooper, U.S. Deputy Surveyor,
Under Contract No. 397, Dated July 1, 1881.

Chains	From the Cor. to Tps. 2 & 3 S., Rs. 34 & 35 E., N. bet. Secs. 31 & 36. Var. 20° E.	Feet
	Descend & enter timber.	
6.50	A ravine, course E. Ascend.	
10.00	Table land with heavy pine & fir timber, undergrowth the same, with much fallen timber.	
19.25	Center of Daly road, course N.W. & S.E.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, in open timber on W. side of gentle slope, for ¼ Sec. Cor., marked ¼ S., on the E. & W. faces, from which, A tamarack, 12 ins. diam., brs. N.66°W., 67 lks. dist., marked ¼ S., B.T. A pine, 8 ins. diam., brs. S.7°E., 27 lks. dist., marked ¼ S., B.T. Var. 20°45'E.	
50.00	Descend through open timber, some down timber and dense undergrowth.	
80.00	A fir, 18 ins. diam., which I mark, T.2 S., S.30 on N.E. R.35 E., S.31 on S.E. R.34 E., S.36 on S.W. and S.25 on N.W. faces, with 1 notch on S. and 5 notches on N. edges, from which, A fir, 16 ins. diam., brs. S.60°E., 13 lks. dist., marked T.2 S., R.35 E., S.31, B.T. A fir, 18 ins. diam., brs. N.43°E., 42 lks. dist., marked T.2 S., R.35 E., S.30, B.T. A fir, 20 ins. diam., brs. N.44°W., 38 lks. dist., marked T.2 S., R.34 E., S.25, B.T. A pine, 8 ins. diam., brs. S.31°E., 35 lks. dist., marked T.2 S., R.35 E., S.31, B.T. Land; high mountain tableland. Soil; gravelly 2nd rate. Timber; pine, fir & tamarack.	